


MODIKWA PLATINUM MINE

FACILITY VISIT
4 March 2003



Agenda


Mike Jooste : Business Leader

- **Location and setting**
- **Project parameters**
- **JV structure and management**
- **Mine layout and mining method**
- **Geology and exploration**
- **Training and development**
- **Socio- economic development**



Ron McGregor : Business Area Leader : Process

- **Concentrator and metallurgy**

MODIKWA
PLATINUM




- Bushveld Complex
- Amplats Mines
- Impala Mines - Gencor
- Lonrho Mines
- Goldfields Mines - Northam




MODIKWA LEASE AREA

Current =



Modikwa Platinum Mine



Key Parameters

- Mining authorisation covers the farms Driekop, Maandagshoek, Hendriksplaats, Onverwacht & Winterveld
- First phase comprises 2 decline shaft systems on Onverwacht and Hendriksplaats + adit system on Onverwacht Hill
- Production on steady state – 200 ktm, 162 koz Pt/annum
- 2 100 employees
- Budget – R1,8 billion (real 2003 terms)
- Plant commissioned – August 2002
- Full production – 2004


Modikwa (Jan 2002)



Modikwa (Jan 2003)



Joint Venture



JV Management Structure

EXCO

Policy decisions

Equal number of members appointed from
ARM and Anglo Platinum
Chairperson - P Motsepe

STEERING COMMITTEE

Technical decisions

Members with requisite skills appointed by the
EXCO's of ARM and Anglo Platinum

OPERATIONAL COMMITTEE

Operational decisions

On mine operational team


Management Team

- **Business Leader – M Jooste**
- **Area Leader North – M da Costa**
- **Area Leader South – G Strong**
- **Area Leader Process – R McGregor**
- **Area Leader Info & Financial – E Cilliers**
- **SHE Leader – F Veltman**
- **Area Leader Logistics – A Olivier**
- **Area Leader ERM – B van Rhyn**
- **Other : HR, Training, IR, Community**

Basic Layout of Decline Shafts

- **Trackless material decline (5m x 5m)**
- **Conveyor decline (4,5m x 4m)**
- **Chairlift decline (4m x 4m)**
- **Four production levels and a RAW**
- **Levels accessed by means of ramps from the material decline**
- **Main drives developed on reef**

Decline Shaft Layout



Declines and Drives

- **Developed using mechanised equipment**
- **Equipment:**
 - **Axera D06 Drill Rigs**
 - **Axera D06 Roofbolters**
 - **Toro 1250 LHD's**
 - **Toro D50 Dump Trucks**
 - **Fermel Utility Vehicles**

Twin Boom Drill Rig



Roof Bolter



12.5 ton Load Haul Dumper



50 ton Dump Truck



Equipment Maintenance

- **Tamrock contract in place**
- **Workshops on site**
- **SAP Planned Maintenance system**

Winzes

- **Mechanised development using low profile machines**
- **Equipment:**
 - **Axera LP Drill Rigs**
 - **EJC 115 Lhd's**
- **Where reef dips exceed 15° winzing is done conventionally**


Raising and Stopping


Raising :

- **Conventional raising with handheld machines**

Stopping :

- **Down-dip panels $\pm$ 28m face length**
- **Conventional stopping**
 - **Handheld machines**
 - **Scraper cleaning**
 - **Blasting with Anflex and shocktube**





Some Design Criteria

- **Two shaft systems – approx. 3,2km's apart**
 - One material and one conveyor shaft
 - Chairlift decline added later
 - Hillside adit mining
- **200 000 ton per month concentrator**
 - Natural fines circuit
 - Autogenous / ROM ball milling
 - Chrome silica circuit
- **Central infrastructure**
 - Offices and training facility

Some Design Criteria

- **Conventional stoping**
 - Raises
 - Down dip stoping
 - Handheld drills
- **High productivity mine:**
 - Continuous operations
 - Two panel cycle
 - No night shift on the reef plane
 - Concentrator has high level of process control


GEOLOGY and EXPLORATION

Geology


- **Lithological setting and optimal stope cut**
- **Geological model and mine design optimisation**
- **Exploration drilling programme**

Eastern Bushveld :

Stratigraphic column in proximity of UG2 at Modikwe




Optimal Stopping Cut (per shaft area)




* RGSW= Recommended Geological Stopping Width


Geological Model – North Mine



Geological Model – South Mine



Geological Model – Hill Operations



Mine Design Optimisation

- **Structural features including slumps, potholes, shear zones/faults, undulating reef, and pegmatite replacement bodies although challenging are being successfully addressed**
- **An increased drilling density is enabling optimal positioning of drives and access ramps.**
- **Dip drives are in place to fit optimal raise backs**
- **The base of the regolith / UG2 interference line is determined ahead of mining**

Mine Design Optimisation

- **Groundwater modeling and management is in place. Surface appears dry – small secondary aquifers do exist - dewatering programme in place**
- **Geological logging and modelling is in place and assists in optimal cut selection**

Exploration Drilling Programme

Planned drilling for 2003 :

- **Surface drilling** **24 600 m**
- **Underground drilling** **14 600 m**
- **Total** **39 200 m**
- **Density matched to achieve optimal mine design**

**“Create One Mine
One Culture”**

Behavioural Department

Goal: To develop every employee to his / her full potential. This will ensure world-class performance with world-class safety record

Areas of Focus:

- **Self Mastery** (Focus on Personal Qualities)
- **Team Mastery** (Focus on Team Qualities)
- **Business Mastery** (Focus on Business Principles)
- **Behavioural Safety** (Focus on Critical Safe Behaviour)



Behavioural Process – Methods

- **Behavioural and leadership training**
- **Theatre and video's** (A visual training program)
- **Experiential training business program** (Comprehensive business training program)
- **Assessment program** (Alignment with MQA and introduction of Modikwa assessment training program)
- **Behavioural safety interventions and programs**
- **Analysis and continuous involvement**

Socio-Economic Development

- **Employment equity status**
- **SME and HDSA implementation and progress**
- **Socio- Economic Development (SED) and local community involvement**




LEVEL	Male	Female		Male	Female		Male	Female		Male	Female			
E3										1		1	1	0.0
SE1	1		1							6		6	7	14.3
MP2	2		2							10		10	12	17.0
MP1	6		6		1	1				23	2	25	32	28.0
SS2	11	1	12				1		1	79	3	82	95	17.0
SS1	6	1	7							6	5	11	18	67.0
AO2	21	2	23	2		2				55	3	58	83	48.0
AO1	67	5	72	1		1				29	1	30	103	72.0
	114	9	123	3	1	4	1		1	209	14	223	351	41.0

SME and HDSA Implementation

% of contract awarded to HDSA's :

- **Transporting of concentrate : 75%**
- **Transporting of ore : 40%**
- **Hostel administration and catering : 100%**
- **Construction of concrete slabs for mobile offices : 100%**
- **Building of 3 vendor training houses : 100%**
- **Construction of security access gates : 100%**

Socio-Economic Development



ACHIEVEMENTS


Modikwe Safety Summary

<i>Date</i>	<i>Achievement</i>	<i>Section</i>
27-Oct-01	1 000 000 LTI Free Hours	Modikwa
19-Jan-02	1 000 000 LTI Free Hours	Central Logistics
10-Feb-02	1000 Fatality Free Production Shifts	Modikwa
10-Feb-02	1000 Fatality Free Production Shifts	Central Log
23-Mar-02	1000 Fatality Free Production Shifts	North Shaft
23-Mar-02	1000 Fatality Free Production Shifts	South Shaft
30-Mar-02	1000 Fatality Free Production Shifts	Concentrator
26-Apr-02	1 000 000 LTI Free Hours	Concentrator
30-Apr-02	1000 Fatality Free Production Shifts	Onverwacht Hill
26-Jun-02	1 000 000 LTI Free Hours	Central Logistics
9-Jul-02	2 000 000 LTI Free Hours	Concentrator
26-Jul-02	1 000 000 LTI Free Hours	Modikwa
23-Sep-02	2 000 000 LTI Free Hours	Central Logistics
20-Oct-02	1 000 000 LTI Free Hours	Modikwa
23-Nov-02	3 000 000 LTI Free Hours	Concentrator
30-Dec-02	1 000 000 LTI Free Hours	North Shaft

INJURY RATES PROJECT TO DATE

LTIFR – 0.44 RIFR – 0.25

Production Stopping Plan



Achievements

- **Safety at RIFR 0.25 for project to date**
- **Mining of portals initiated March 01**
 - **1st stoping March 02**
 - **Plant commissioned Aug 02**
 - **100 000 tons first month**
 - **59 622m² mined to date**
 - **31 006m developed to date**
- **Achieved 29m face advance (74m²/ise)**
- **1400 local novices recruited and trained**
- **Will achieve full production in by end of 2004**

CONCENTRATOR and METALLURGY

Safety Statistics

Project :

- **2 LTI's (one reportable)**
- **2.81 million manhours without a LTI**

Operations (Staff and plant contractors)

- **0 LTI's**
- **409 days without a LTI (486 010 hours)**

PROJECT AND OPERATIONS TOTAL :

3 297 070

Project Key Dates

- **Earthworks commenced : 8 February 2001**
- **Civil works commenced : 21 May 2001**
- **Steel erection commenced : 12 Dec 2001**
- **E&I erection commenced : 02 Jan 2001**
- **Hot commissioning started : 05 August 2002**

[illegible]

25 July 2001



Milling Circuit



Flotation Cells




Plant Project Statistics

- **Pipelines** 57km
- **Structural Steel** 2 900 T
- **Platework** 1 500 T
- **Motors** 500
- **Pumps** 257
- **Resources** 1 960 people (Peak)

Process


PLANT LAYOUT



Process – Salient Features

- **200 000 tons per month UG2 nominal rating**
- **Original design was based on FAG Milling**
- **Modified to accommodate build-up by ROM ball milling**
- **Separate treatment of chromitite and silicate fractions**
- **Separate treatment of naturally occurring fine size fraction**
- **Automated Process Control Laboratory**


Modikwa Concentrator – Simplified Flow Schematic




Process – Commissioning Progress

- **Commissioned Primary Mill on 5th Aug 2002 in MF2 configuration**
- **Treated 102 000 tons development reef during August**
- **Chrome circuit commissioned 6th September 2002**
- **Achieved 205 000 tons in September through to 230 000 tons in January 2003**
- **Optimisation program underway on existing circuit**
- **Fines specific treatment commissioned at end of 2002**
- **Process Control Laboratory operational by April 2003**

Tons Milled



Recovery 4E





Questions